



South Jersey Technology Partnership

801 W. Preston Avenue
Somerdale, NJ

Proposal

04/30/15

Proposal

Job# 634 to 634

To:

Blackhorse Board Of Education

Proposal No. MB-15-634-Q

580 Erial Rd
Blackwood

NJ 08012

Prepared by: 34

ROOF REPAIRS HIGHLAND
450 Erial Rd
Blackwood NJ 08012

SCOPE OF WORK

WE PROPOSE TO FURNISH AND INSTALL THE FOLLOWING FOR REPAIR OF ROOF AT HIGHLAND HIGH SCHOOL COATING:

- * REFLASH ALL ROOF DRAINS WITH NEW STRIPPING PLY OF GARLAND STRESS PLY E SMOOTH SHEET SET IN GARLAND GREENLOCK ADHESIVE AND STRIP IN WITH GREENLOCK FLASHING CEMENT AND FABRIC
- * FURNISH AND INSTALL NEW CAPE COLLARS AT ALL HVAC UNITS
- * REMOVE AND REPLACE GUTTERS AND DOWNSPOUTS AR RAISED CENTER SECTIONS
- *STRIP IN NEW GUTTERS WITH GARLAND STRESS PLY SMOOTH SET IN GREENLOCK ADHESIVE AND STRIP WITH IN WITH GREENLOCK FLASHING CEMENT AND FABRIC
- * REPLACE WALL FLASHING AT FRONT AND BACK OF RAISED CENTER WITH GARLAND VERSI I PLY 40 SET IN GARLAND GREENLOCK ADHESIVE AND TOP PLY OF GARLAND STRESS PLY E MINERAL SET IN GREEN LOCK ADHESIVE
- * REMOVE AND REPLACE WET INSULATION NOTED APPROXIMATELY 800 S/ FT INSTALL NEW INSULATION TO MATCH EXISTING AND COVER BOARD SET IN GARLAND INSUL LOCK ADHESIVE AND GARLAND FLEX 80 AND STRESS PLY E SMOOTH SET IN WEATHER KING ADHESIVE. FLOOD COAT THE AREA WITH GARLAND WEATHER SCREEN AND ADHERE AGGREGATE.
- *REPLACE LEAD VENT AND STRIP IN WITH GARLAND GREENLOCK FLASHING CEMENT AND FABRIC
- *FURNISH AND INSTALL NEW WALL PANELS ON ELEVATOR REPLACE THE BASE FLASHING WITH GARLAND VERSI PLY 40 AND STRESS PLY E MINERAL SET IN FLASHING ADHESIVE
- * PROVIDE DUMPSTER FOR OUR TRASH
- * PROVIDE CRANE FOR LOADING AND UNLOADING OF MATERIALS.

LABOR & MATERIALS

85,800.00

ALLOWANCE

Proposal

04/30/15

Continued...

2,000.00

RE-ROOFING

4,000.00

Grand Totals:

\$

91,800.00